Faldes











PLATE EXCHANGER

High-efficiency polymeric membrane counter-flow ERV

CASING (Standard)

Material: 24-gauge galvanized steel Drain connections: optional Duct connections: 5"(127 mm) Insulation: EPS molded polystyrene

Length: 23" (584.2 mm) Height: 19" (482.6 mm) Width: 16" (406.4 mm) Weight: 49 lb (22 kg)

Exhaust Damper: Closed by gravity Fresh air Damper: Motorized

Swivel ports for horizontal, vertical, oblique or mixed

installations.



MOUNTING

Mounting chains included Wall mounting optional (P/N 699878)



ELECTRICAL SPECIFICATIONS

120 V, 60 Hz, 145 W, 2.46 A



FILTERS

(Standard)

Quantity:

2 washable MERV 6 filters (P/N 699771) Optional filter types: MERV 8 (P/N 699772), MERV 13 (P/N 699881)

InspirAIR® ELITE

ERV

EK150-TQX

154 CFM at 0.4 in.w.g




















DEFROST

Automatic Programmed Recirculation: Cycles are controlled by a temperature sensor when the outside temperature drops below 17.6°F (-8°C).

WARRANTY

Limited 5 years on the cores and all covered components.

WALL CONTROLS

Low voltage dry contact (24VAC) for interlock with heating and cooling systems. For more details, please refer to the wall control specification sheets.



Digital Multifunction Control (P/N 611242-FC)



LCD Electronic Multifunction Control (P/N 611227)



20/40/60 Minute Timer (P/N 611228)




Speed Control (Low/Intermittent/High) (P/N 611229)




Mode Control (Recirculation) (P/N 611230)




Page 2 | EK150-TQX



FRONT VIEW




SIDE VIEW



EK150-TQX: PERFORMANCE

EK150-TQX Ventilation Performance



Thermal Performance – EK150-TQX									
Supply Tem- perature		Net Airflow		Power Consu- med	Sensible Recovery	Adjusted Sensible	Latent Recovery/	Total Recovery	
°F	°C	CFM	L/s	(W)	Efficiency	Recovery Efficiency	Moisture Transfer	Efficiency	
Heating									
32	0	50	23	23	83%	86%	74%	-	
32	0	65	31	29	83%	86%	73%	-	
-13	-25	67	31	50	75%	77%	71%	-	
Cooling									
95	35	65	31	29	-	-	88%	83%	

Project:	Architect:
Location:	Engineer:
Model #:	Contractor:
Quantity:	Comments:
Submitted By:	
Date:	





