



PLATE EXCHANGER

High Latent Transfer

CASING (Standard)

Material: 24-gauge galvanized steel

Drain connections: optional

Duct connections: 5" (127 mm)

Insulation: EPS molded polystyrene

Length: 23" (584.2 mm)

Height: 19" (482.6 mm)

Width: 16" (406.4 mm)

Weight: 41 lb (19 kg)

Exhaust Damper: Closed by gravity

Fresh air Damper: Motorized

Swivel ports for horizontal, vertical, oblique or mixed installations.

MOUNTING



Mounting chains included

Wall mounting optional (P/N 699921)

ELECTRICAL SPECIFICATIONS



120 V, 60 Hz, 187 W, 2.51 A

FILTERS



(Standard)

Quantity:

2 washable MERV 6 filters (P/N 70023)

Optional filter types: MERV 8 (P/N 70024),

MERV 13 (P/N 70025)

InspirAIR® ELITE ERV

E170-TQG

171 CFM at 0.4 in.w.g



UNIT

CORE



BLOWERS & MOTORS

Two motorized impellers (backwards inclined)

Quick-connect motors for easy and efficient maintenance
PSC motor



DEFROST

Automatic Programmed Recirculation: Cycles are controlled by a temperature sensor when the outside temperature drops below -5°C (23°F)

WARRANTY

Limited 5 years on the cores and all covered components.

WALL CONTROLS

Low voltage dry contact (24VAC) for interlock with heating and cooling systems. For more details, please refer to the wall control specification sheets.



Digital Multifunction Control (P/N 611242-FC)



LCD Electronic Multifunction Control (P/N 611227)




20/40/60 Minute Timer (P/N 611228)




Speed Control (Low/Intermittent/High)
(P/N 611229)



Mode Control (Recirculation) (P/N 611230)



E170-TQG: PERFORMANCE



Thermal Performance – E170-TQG								
Supply Tem- perature		Net Airflow		Power Con- sum- ed (w)	Sensible Recovery Efficiency	Adjusted Sensible Recovery Efficiency	Latent Recovery/ Moisture Transfer	Total Recovery Efficiency
°F	°C	CFM	L/s					
Heating								
32	0	36	17	60	78%	90%	76%	-
32	0	50	23	70	75%	84%	71%	-
32	0	65	30	81	72%	80%	66%	-
32	0	80	37	102	69%	78%	63%	-
-13	-25	67	31	106	63%	67%	64%	-
Cooling								
95	35	65	30	80	-	-	52%	51%

Project:		Architect:	
Location:		Engineer:	
Model #:		Contractor:	
Quantity:		Comments:	
Submitted By:			
Date:			